BRUHATH BANGALORE MAHANAGARA PALIKE,

Office of the Executive Engineer Dasarahalli Division,

Shedule -B

NAME OF WORK: Extension of Pipelines in Missing bits & providing Water supply in Ward No.12, Shettyhalli sub Division

Sl. No	Description of work	Unit	Qty	Sanctioned rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications and direction of Engineer- in-charge.	cum	550.8	316.94	
2	Providing and installing at site work P.V.C. Pipes including cost of pipes and specials and labour,including lowering into trenches,laying true to line,level and perfect linking at joints lead proof including jointing of approved type with all labour and lift charge, handling charges with all leads,including encasing the pipe around to a depth not less than 15cms with gravel or selected earth available from the excavation etc complete as per specification and direction of Engineer- in-charge.	mtr	1020	107.12	
3	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications and direction of Engineer- in-charge.	cum	550.8	128.26	
4	Hire charges of water tanker for supplying water through water tanker at water scared area as per the direction of Engineer incharge	day	360.00	412.00	

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Zone, Bangalore-57.

Scanned by CamScanner

5	Supply of Water etc complete as per specification and direction of Engineer- in-charge.	**KL**	**10800.00**	40.00	
6	Engaging Tractor 50 HP Capacity for supplying water through water tanker at water scared area etc complete as per specification and direction of Engineer- in-charge.	**day**	**360.00**	2129.00	

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner